

# Laguna Conceptual Restoration Design

## Task 4: Final/Preferred Habitat Restoration Concept



# Presentation Outline


- Purpose and Objectives
- Site Map
- Project Design Considerations and Alternative Analysis
- Preferred Alternative Overview
- Wetland Channels
- Levees & Roads
- Firebreaks
- Water Delivery & Water Control Structures
- Re-vegetation and Habitat
- Water Operations Management
- Cost Summary
- Additional Information Needs
- Timeline for Project Development

## Purpose & Objectives

- Large Scale Riparian and Marsh Restoration/Enhancement
- Determine the cost effectiveness and technical feasibility of a mosaic of habitat types
- Provide evaluation of three enhancement alternatives
- Provide detailed analysis of preferred enhancement alternative

# Project Site Map

- Project Area – 1050 acres
- Reach Length – 4.3 miles
- Existing Conditions
  - Extensive/dense tamarisk monoculture



# Project Design Considerations

- Up to 100 cfs available for project use
- Habitat Targets
  - Open Water/Marsh: 50 – 100 ac
  - Cottonwood/Willow: >200 ac
  - Upland(mesquite): <500 ac
  - Include specific habitat for T&E species
- No detrimental effect on existing Mittry Lake or Old River Channel Habitats
- Minimize impacts to existing operations (sluicing, dredge disposal, water delivery, etc.)
- Minimize both initial construction and long-term operating costs

# Target Habitats

Open Water/Marsh: 50 – 100 ac



Cottonwood/Willow: >200 ac



Upland (Mesquite): <500 ac

# Target Species



California Black Rail

Yuma Clapper Rail



Southwestern Willow Flycatcher



Yellow Billed Cuckoo



Yuma Hispid Cotton Rat



Colorado River Cotton Rat



Western Least Bittern




# Alternative Analysis

- **Task 1** – Provide 3 draft conceptual alternatives to BOR
  - Water Delivery and Control
  - Grading and Habitat Layout
  - Planting
  
- **Task 2** – Refine alternatives and present to MSCP planning team
  
- **Task 3** – Refine and present draft preferred concept to MSCP planning team
  
- **Task 4** – Address comments and present to MSCP Steering Committee


# Preferred Alternative Overview

- Operate as a managed, leveed wetland rather than a river system to maximize limited water resource
- Use existing overflow channels through project area to minimize excavation
- Use pulse flows to mimic flooding
- Requires water control structures to manage water levels





# Wetland Channel Improvements


- Provides the topography to support water conveyance and vegetation/habitat
- Reach 1 & 2 primary and secondary channels
- Reach 3 channels
- Enhance Historic River Channels
- Channel layout utilizes existing channel topography



# Reach 1, 2, & 3 Typical Cross Sections




- Channel Elevations
- Base Flow Water Depth
- "Pulse" Flow Water Depth



# Historic River Channel Improvements



Existing Condition




Planned Condition


- Provide ~80 acres of shallow marsh habitat with no flow fluctuations
- Moderate grading to deepen and widen existing channel
- Soil moisture supported by existing water table
- Can be flushed with occasional flows from Reach 1 (optional steady flow)

## Levees and Access Roads

- New levees & roads constructed using material from channel excavation (additional spoil areas between braided channels)
- Provides access to water control structures and the interior of the site and ties into existing access road system
- Allows Reaches 1 and 2 to be operated at different water levels
- Provides separation between Historic River Channel and the Project Area
- Provides separation between Laguna Dredge Disposal Area and the Project Area while providing additional access to the Dredge Disposal Area



Typical Levee/Road Section




## Fire Control/Fire Breaks

- Roads and levees provide equipment access and fire breaks
- Transitional zone vegetated primarily with salt grass acts as a firebreak
- Open water zone provides additional firebreak




Salt Grass & Open Water




## Water Delivery System: Gravity Pipeline

- System conveys 100 cfs base flow to the project site
- Low maintenance gravity system
- Independent delivery with limited impacts to the existing dam operations
- High quality water (low salinity/sediment load) at take out
- Piped system reduces evaporation and infiltration




## Water Control Structures: Plan View

- Three (3) structures to control water surface elevations within the new units
- WCS#1 and WCS#2: In-line with Reach 1, 2, & 3
- WCS#3: Turn-out for the Historic River Channel




# Water Control Structures: Overshot Gates



- Ease of adjusting water surface elevation (potential to automate)
- Precise water elevation control (0.25 inch increments)
- Minimal leakage
- Gate allows surge flows and debris to pass

# Proposed Mittry Lake Inlet Canal Feed Structure

- Analysis requested by AZGFD to enhance Mittry Lake habitat
- Utilize smaller overshot gate structure
  - Would allow surplus water to be diverted from Upper Unit (Reach 1) to Mittry Lake Inlet Canal.
  - Would require automation to provide steady flows into Mittry Lake Inlet Canal.
  - May require modifications to Mittry Lake Outlet Control and/or the proposed Laguna Inlet Water Delivery Pipeline.



# Revegetation Design

- Remove existing nonnative species
- Planting based on topography, moisture and salt tolerance of plants
  - Bands of vegetated communities relative to water level
- Utilize pulse flows as irrigation for cottonwood/willow
- Utilize temporary drip irrigation for mesquite planted on higher terraces
- High density planting of vegetation plugs, poles, seeds and rooted materials for rapid establishment of cover.
- Will require maintenance and weed management for 2 – 3 years
- Plantings are expected to be self sustaining in long-term
- Utilizes 15 years of experience with planting in LCR by Fred Phillips Consulting



*Prosopis glandulosa var. torreyana*  
*Populus fremontii*  
*Distichlis spicata*  
*Sporobolus airoides*

*Atriplex lentormis*  
*Salix exigua*  
*Scirpus olneyi*  
*Scirpus acutus*

*Allenrolfea occidentalis*  
*Salix goodingii*  
*Anemopsis californica*  
*Schoenoplectus californicus*




# Revegetation Design Primary Channels




**MSCP Laguna Restoration**  
Primary Channel Cross Section

Date: 5/28/09  Scale: 1" = 12'

# Revegetation Design Secondary Channels





**MSCP Laguna Restoration**

Reach 1 Concept Drawing

Date: 8/18/09


# Habitat Acreages


	OPEN WATER	DEEP MARSH	TRANSITION ZONE/ FIRE BREAK	COTTONWOOD/ WILLOW	MESQUITE
Reach 1	46	63	35	150	55 (no irrigation) 143 (irrigation)
Reach 2	15	21	31	223	20 (no irrigation) 11 (irrigation)
Reach 3	4	10	8	14	0 (no irrigation) 96 (irrigation)
Historic River Channel	0	0	81	14	11 (no irrigation) 6 (irrigation)
<b>Project Totals</b>	<b>65</b>	<b>94</b>	<b>155</b>	<b>401</b>	<b>86</b> (no irrigation) <b>256</b> (irrigation)
<b>MSCP Targets</b>		50-100		>200	<500




# Water Operations Management Overview

- Utilize overshot gates to manage water surface elevations in Reach 1 and Reach 2
  - Overshot gates allow easy water elevation adjustment
  - Will allow irrigation of cottonwoods & willows at higher elevations through simulated flood events (pulse flows)
  - Reach 1 and Reach 2 are in-series cells – water management will require choreography of Reach 1 and Reach 2 gates
- Adaptive management
  - Adjust operation as seasonal habitat and wildlife needs dictate
  - Adjust operation as vegetation matures






# Conceptual Operation Hydrograph



1. Reach 1 overshoot gate "closed". Flows to Reach 2 are cut-off.
2. Reach 1 fills. With no influx, Reach 2 loses water to ET/EVAP/Seepage
3. Reach 1 hits "pulse" water surface and begins to overtop its overshoot gate. Reach 2 overshoot gate "closed" and Reach 2 begins to fill with overflow water from Reach 1.
4. Reach 1 is kept at "pulse" water surface for two days, allowing soils to saturate and reach deep pot plantings of mesquite and cottonwood. Reach 2 fills to it's "pulse" water surface elevation.
5. Reach 1 overshoot gate is adjusted to pre-pulse position and water in Reach 1 is drawn-down. Reach 2 is kept at "pulse" water surface for two days (see #4, Reach 1). Reach 2 gate is adjusted to maintain pulse water surface elevation and allow for additional draw-down flows from Reach 1.
6. Reach 1 continues to draw down. Reach 2 overshoot gate is adjusted to pre-pulse position and water in Reach 2 is drawn-down.
7. Next irrigation cycle begins ~ 6.2 day gap between pulses

## Conceptual Operation Hydrograph



- Conceptual Model
  - Modeled the month of July (highest ET/EVAP rates)
  - Fill rates will change with ET/EVAP/Seepage rates
  - System operation will require tweaking – overshot gates allow that
- Long-term Adaptive management
  - Once vegetation is established and can be stressed, pulse events can be decreased
  - Example: Steadier flows are beneficial for black rail nesting (April – June)

## Conceptual Water Budget

POST-DEVELOP ET/EVAP (acre-ft/yr)*	POST-DEVELOP SEEPAGE (acre-ft/yr)**	POST-DEVELOP TOTAL (acre-ft/yr)	PRE-DEVELOP ET (acre-ft/yr)*
5900	1150	7050	5800

\* Evaporation rates per Cooley, K.R., 1970, Evaporation from open water surfaces in Arizona: University of Arizona College of Agriculture, folder 159. Evapotranspiration rates for different habitat types provided by BOR (average of years 2005-2007)

\*\* Seepage rate calculations for Reach 2 based on groundwater and soil log data for well AP-103-08. Reach 1 groundwater is at or above the proposed channel invert so seepage is assumed to be minimal.

## Conceptual Level Cost Estimate Summary

Project Component	Final Design & Construction Cost	O & M Cost (50-Year Life Cycle)	Component Total
Earthwork	\$12.4M	\$0.5M	\$12.9M
Water Delivery & Control Structures	\$2.3M*	\$0.3M	\$2.6M
Revegetation	\$4.2M	\$2.9M**	\$7.1M
<b>PROJECT TOTAL</b>	<b>\$18.9M</b>	<b>\$3.7M</b>	<b>\$22.6M</b>

\* Does not include the Mittry Lake Inlet Canal Structure

\*\* Assumes 5-years of intensive work at the beginning of the project, minimal work thereafter

## Additional Information Needs

- Additional Monitoring Wells along Proposed Channels
  - Groundwater information
  - Soil Information (salinity, texture, nutrients)
- Existing Infrastructure Information
- Existing Vegetation information
- Detailed Topographic Survey
- Final Design and Bid Package

# Timeline for Project Development

